

NEW TWO STORY SINGLE FAMILY HOUSE WITH ATTACHED ADU AND DETACHED 2 CAR GARAGE

BNDS

21060 HOMESTEAD RD, CUPERTINO , CA 95014 T: 650.665.0435

DATE

02/20/2025



CONSULTANT BEHROOZ NEMATI

8 NEWHALL RD. RLINGAME CA 9401


APPROVED ARCHITECTURAL & SITE APPLICATION: S-19-033

REV	DATE	DESCRIPTION
	1.12.2022	BUILDING PERMIT
2	07/31/2025	PLANNING
_		
DAT	E	6.1.2021
PRC	JECT NO.	F21.1
SHE	FT TITLE	

COVER SHEET

ET NO.

A0.0



BIDDING - NOT USED.

OWNERSHIP OF CONTRACT DOCUMENTS

- Q architects is the author & owner of its instrument of service including this set of dwgs & specifications. ${ t Q}$ ARCHITECTS RETAINS ALL COMMON LAW, STATUTORY & OTHER RESERVED RIGHTS, INCLUDING COPY RIGHTS TO THIS INSTRUMENT OF SERVICE. THEREFORE, THIS DWG. SET SHALL NOT BE REPRODUCED, DISCLOSED OR USED IN ANY WAY WITHOUT THE WRITTEN CONSENT OF Q ARCHITECTS.
- 2. contractor, sub-contractors & suppliers are authorized to use & reproduce this instrument of service | 5. NOT USED. ;olely & exclusively for the execution of the work. All copies made under this authorization shall bear the |COPYRIGHT NOTICE, IF ANY, SHOWN ON THE INSTRUMENT OF SERVICE. THE CONTRACTORS, SUB-CONTRACTORS &, SUPPLIERS | MAY NOT USE THE INSTRUMENT OF SERVICE ON OTHER PROJECTS OR FOR ANY ADDITIONS TO THE PROJECT OUTSIDE OF THE SCOPE OF WORK WITHOUT THE SPECIFIC WRITTEN CONSENT OF THE ARCHITECTS.

CONTRACT DOCUMENTS, FIELD CONDITIONS & WORK

- ALL CONTRACT DOCUMENTS INCLUDING DWGS. & SPECIFICATIONS SHALL BE USED IN CONCERT W/ EACH OTHER. THE contractor, subcontractors & material suppliers shall refer to the dwgs. & specifications as a whole when DETERMINING THE CONSTRUCTION REQUIREMENTS FOR THE WORK.
- 2. THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING THE EXTENT, NATURE & SCOPE OF WORK DESCRIBED IN THE CONTRACT DOCUMENTS. IF THE CONTRACTOR DISCOVERS ANY DISCREPANCIES BETWEEN THESE DOCUMENTS, THE CONTRACTOR SHALL PROMPTLY NOTIFY THE ARCHITECT IN WRITING FOR ANY CLARIFICATIONS, CORRECTIONS OR ADJUSTMENTS. NO ALLOWANCE SHALL BE MADE FOR INCREASED COSTS INCURRED DUE TO LACK OF PROPER COORDINATION.
- 3. The Contractor is responsible to provide all labor & materials necessary to execute all work as shown on THE DWGS. W/ THE EXCEPTION OF THOSE ITEMS AS NOTED AS SEPARATE CONTRACT (N.I.C.). HE SHALL BE RESPONSIBLE FOR COORDINATING THIS WORK W/ THAT OF ALL TRADES, INCLUDING TRADES OPERATING UNDER SEPARATE CONTRACT W/ THE
- 4. THE CONTRACTOR IS RESPONSIBLE FOR THE DISTRIBUTION OF DWGS. & WHERE APPLICABLE SPECIFICATIONS, TO ALL TRADES UNDER HIS SUPERVISION. AFTER THE EXECUTION OF THE CONSTRUCTION CONTRACT W/ THE OWNER, THE AWARDED CONTRACTOR SHALL RECEIVE THE COMPLETE SET OF DOCUMENTS AS "ISSUED FOR CONSTRUCTION"
- 5. PRIOR TO COMMENCING WORK, THE CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD VERIFICATION OF ALL (E) CONDITIONS & DIMENSIONS IN THE FIELD, INCLUDING ALL GOVERNING DIMENSIONS AT THE BUILDING. THE CONTRACTOR SHALL EXAMINE ALL ADJOINING WORK OR AREAS UPON WHICH THE PERFORMANCE OF HIS WORK IS IN ANY WAY DEPENDANT.
- 6. THE CONTRACTOR SHALL PROMPTLY & BEFORE THE COMMENCEMENT OF THE AFFECTED WORK, NOTIFY THE ARCHITECT OF ANY ERRORS, OMISSIONS OR INCONSISTENCIES IN THE CONTRACT DOCUMENTS, ANY DIFFERENCES BETWEEN FIELD MEASUREMENTS OR CONDITIONS & THE CONTRACT DOCUMENTS, OR FOR NON-CONFORMITIES OF THE CONTRACT DOCUMENTS TO APPLICABLE LAWS, STATUTES, ORDINANCES, CODES, RULES AND REGULATIONS, & LAWFUL ORDERS OF PUBLIC OFFICIALS.
- 7. THE CONTRACTOR SHALL REQUEST FOR ANY REQUIRED INFORMATION THAT IS NOT SHOWN ON THE DRAWINGS OR OTHER CONTRACT DOCUMENTS FROM THE ARCHITECT PRIOR TO BID OR COMMENCEMENT OF ANY WORK.
- 8. THE CONTRACTOR SHALL PROVIDE COMPLETE WORK. ANY OMISSION IN CONTRACT DOCUMENT INCLUDING NOTES & ILLUSTRATION ON THE DWGS. SHALL NOT BE CONSTRUED AS RELIEVING THE CONTRACTOR OF SUCH RESPONSIBILITIES AS ARE IMPLIED BY THE SCOPE OF THEIR WORK EXCEPT FOR ITEMS SPECIFICALLY NOTED IN THE CONTRACT DOCUMENTS.
- 9. ANY WORK PERFORMED IN CONFLICT W/ ANY PART OF THE CONTRACT DOCUMENTS OR ANY CODE REQUIREMENTS SHALL BE CORRECTED BY THE CONTRACTOR AT HIS OWN EXPENSE AND AT NO EXPENSE TO THE OWNER OR ARCHITECT.

PERMIT FEES, NOTICES, & COMPLIANCE W/ THE LAWS & INDUSTRY STANDARDS

- THE CONTRACTOR SHALL PERFORM ALL WORK IN ACCORDANCE W/ THE CALIFORNIA CODE OF REGULATIONS (TITLE DOCUMENTS), & ALL OTHER LOCAL CODES & ORDINANCES OF THE GOVERNING AUTHORITY HAVING JURISDICTION & AS IDENTIFIED UNDER APPLICABLE CODES ON SHEET A0.0 COVER SHEET. ALL WORK SHALL ALSO CONFORM TO ALL APPLICABLE CITY, COUNTY, STATE, FEDERAL CONSTRUCTION SAFETY & SANITARY LAWS, CODES, STATUES & ORDINANCES. THE CONTRACTOR SHALL REPORT PROMPTLY ANY DISCREPANCIES, VARIATIONS OR OMISSIONS IN THE CONTACT DOCUMENTS TO THE ARCHITECT.
- 2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PAYING FEES & SECURING ALL REQUIRED PERMITS, LICENSES, NOTICES & INSPECTIONS AS REQUIRED BY GOVERNMENT AGENCIES FOR THE PROPER EXECUTION& COMPLETION OF THE WORK AFTER THE EXECUTION OF THE CONTRACT & LEGALLY REQUIRED AT THE TIME BIDS ARE RECEIVED OR NEGOTIATIONS CONCLUDED.
- 3. THE CONTRACTOR SHALL COMPLY W/ & GIVE NOTICES REQUIRED BY APPLICABLE LAWS, STATUES, ORDINANCES, CODES, RULES & REGULATIONS, OR LAWFUL ORDERS OF PUBLIC AUTHORITIES APPLICABLE TO PERFORMANCE OF THE WORK.
- 4. IF THE CONTRACTOR PERFORMS WORK KNOWING IT TO BE CONTRARY TO APPLICABLE LAWS, STATUTES, ORDINANCES, CODES, RILLES & REGULATIONS OR LAWFUL ORDERS OF PUBLIC AUTHORITIES, THE CONTRACTOR SHALL ASSUME APPROPRIATE RESPONSIBILITY FOR SUCH WORK & SHALL BEAR THE COSTS ATTRIBUTABLE TO CORRECTION.
- 5. THE CONTRACTOR SHALL COMPLY W/ THE RULES & REGULATIONS OF THE CITY GOVERNING THE WORK TO AVOID CONFLICT & INTERFERENCE WITH NORMAL OPERATIONS, IN TERMS OF PERMITTED HOURS FOR DEMOLITION & CONSTRUCTION IN ADDITION TO THE MANNER OF HANDLING CONSTRUCTION MATERIALS, EQUIPMENT & DEBRIS.
- 6. ALL WORK SHALL BE PERFORMED BY SKILLED & QUALIFIED CONTRACTORS & IN ACCORDANCE W/ THE HIGHEST STANDARDS OF QUALITY & BEST PRACTICES OF EACH TRADES & FOR THE RELEVANT WORK IN GENERAL.

SUPERVISION & CONSTRUCTION PROCEDURES THE CONTRACTOR SHALL BE SOLELY & COMPLETELY RESPONSIBLE FOR, & HAVE CONTROL OVER CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES & PROCEDURES, & FOR COORDINATING ALL PORTIONS OF THE WORKS UNDER THE

- 2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR INSPECTION OF PORTIONS OF COMPLETED WORK TO DETERMINE THAT SUCH
- PORTIONS ARE IN PROPER CONDITION TO RECEIVE SUBSEQUENT WORK.
- 3. THE CONTRACTOR MUST FIELD VERIFY ALL MEASUREMENTS PRIOR TO ORDERING, FABRICATION OR INSTALLATION OF ANY PORTIONS OF THE WORK. NOTIFY ARCHITECT IN WRITING OF ANY DISCREPANCIES PRIOR TO COMMENCEMENT OF THE WORK.
- 4. THE CONTRACTOR SHALL ESTABLISH THE LOCATIONS OF (N) WALL LAYOUTS IN THE FIELD IN CHALK LINE OR TAPE AS APPROPRIATE. THE CONTRACTOR SHALL WALK THE ENTIRE PROJECT AREA W/ THE TENANT (IF ANY) OR OWNER & /OR THE ARCHITECT TO CONFIRM THE SIZE, SHAPE, & PLACEMENT OF ALL NEW ROOMS & AREAS WHERE OCCUR; FOR THE TENANT'S (IF ANY) & THE OWNER'S APPROVAL PRIOR TO FRAMING ANY NEW WALL. THE CONTRACTOR SHALL NOTIFY THE ARCHITECT IF THE TENANT REQUESTS FOR ANY CHANGES TO THE APPROVED NEW WALL LAYOUT.

ONTRACTOR'S CONSTRUCTION & SUBMITTAL SCHEDULES NOT USED

tting / fitting / patching / chasing / drilling / demolishing not used

CLEAN-UP - NOT USED.

PREMISES AND PROTECTION OF PERSONS AND PROPERTY

- THE CONTRACTOR SHALL BE SOLELY & COMPLETELY RESPONSIBLE FOR THE CONDITIONS OF PREMISE ON WHICH THE WORK IS PERFORMED & FOR THE SAFETY OF ALL PERSONS & PROPERTY ON THE PREMISE DURING THE PERFORMANCE OF THE CONTRACT. THIS REQUIREMENT SHALL NOT BE LIMITED TO NORMAL WORKING HOURS, BUT SHALL APPLY CONTINUOUSLY.
- 2. THE CONTRACTOR SHALL EXERCISE UTMOST CARE TO ENSURE THAT THE PREMISE SHALL BE PROTECTED FROM DAMAGE THAT MAY OCCUR DUE TO THIS WORK. THE CONTRACTOR SHALL PROVIDE PROTECTION TO ALL (E) WORK, ALL MATERIALS (E) ON THE PREMISE & (N) WORK AREAS. ANY DAMAGE DUE TO THIS WORK SHALL BE REPAIRED, REPLACED OR PATCHED AT THE DISCRETION OF THE OWNER. THE CONTRACTOR SHALL BEAR FINANCIAL RESPONSIBILITY FOR SUCH DAMAGE & ANY SUCH WORK UNDERTAKEN TO RECTIFY IT.
- 3. THE CONTRACTOR SHALL MAINTAIN PROTECTION FOR ALL TRAFFIC AREAS OF THE PREMISE TO BE USED DURING THE PERFORMANCE OF THE WORK. THE CONTRACTOR SHALL RECTIFY ANY DAMAGE CAUSED BY HIS OPERATIONS.

- THE CONTRACTOR IS RESPONSIBLE FOR COMPLIANCE W/ ANY REQUIREMENTS INCLUDED IN THE CONTRACT DOCUMENTS REGARDING HAZARDOUS MATERIALS OR SUBSTANCE.
- 2. THE CONTRACTOR SHALL REPORT TO THE OWNER & ARCHITECT IN WRITING OF ANY MATERIALS SUSPECTED OF CONTAINING HAZARDOUS THAT ARE DISCOVERED DURING THE PROGRESS OF THE WORK. WORK IN THAT PARTICULAR AREA SHALL BE SUSPENDED IMMEDIATELY UNTIL THE OWNER TESTS THE SUSPECT MATERIAL & IT IS FOUND TO BE SAFE, OR THE MATERIAL HAS BEEN PROPERLY ABATED.

time & labor - not use

Ompleted work, workmanship & installation- not used UBSTANTIAL & FINAL COMPLETIONS -NOT USED

DEMOLITION NOTES

VERIFY & COORDINATE DEMOLITION WORK W/ OTHER WORK CONTAINED IN THE CONTRACT DOCUMENTS (I.E. OTHER ARCH., STRUCT., MECH., ELECT. & PLUMB. DWGS. & SPECIFICATIONS INCLUDED IN THIS PROJECT). REPORT ANY DISCREPANCIES TO THE ARCHITECT IMMEDIATELY.

. NOT USED.

- remove walls, doors, frames, finishes & accessories as noted or shown. Refer to other disciplines' dwgs. & SPECIFICATIONS FOR ADDITIONAL DEMOLITION INFORMATION.
- 4. (e) utility & support services shall remain at adjacent areas unless & coordinated & approved by the owner. REROUTE & RELOCATE AS NECESSARY TO MAINTAIN SERVICES.

- ACCESS TO REQUIRED (E) EXIT WAYS & EXITS SHALL REMAIN CLEAR & UNOBSTRUCTED AT ALL TIMES. . CONTRACTOR SHALL PROVIDE TEMPORARY BARRICADES OR PARTITIONS AS REQUIRED TO PERFORM SCHEDULE WORK.
- . CONTRACTOR SHALL VERIFY (E) SERVICES TO REMAIN OR TO BE RELOCATED PRIOR TO ANY REMOVAL. 10. (E) ITEMS TO REMAIN, TO INCLUDE BUT NOT LIMITED TO FINISHES, ACCESSORIES, FIXTURES, ETC., SHALL BE PROTECTED AS NECESSARY DURING CONSTRUCTION. ANY AREA DAMAGED DURING THE DEMOLITION WORK BY THE CONTRACTOR SHALL BE RESTORED TO ACHIEVE (E) PREVIOUS CONDITION WITHOUT ANY NOTICEABLE DIFFERENCES TO (E) ADJACENT MATERIALS AT NO

CONSTRUCTION NOTES

ADDITIONAL EXPENSE TO THE OWNER.

. ALL DIMENSIONS SHOWN ARE TAKEN TO THE FACE OF STUDS, U.O.N

10. WHERE 'ALIGN' IS NOTED, ALIGN FINISH SURFACES.

- . ± DIMENSIONS INDICATES LEAST CRITICAL DIMENSIONS. DETERMINE ACTUAL VALUE IN FIELD & NOTIFY ARCHITECT. . DIMENSIONS AT STRUCT.L GRID COLUMNS ARE TAKEN TO THE CENTERLINE OF THE COLUMN, U.O.N.
- i. Do not scale any dimensions, dimensions as shown shall govern, details shall govern over plans & elevations. Large scale drawings shall govern over small scale drawings. Report any discrepancies to the ARCHITECT PRIOR TO THE COMMENCEMENT OF WORK.
-). Refer to the Arch. & engineering dwgs. For placement, orientation & coordination of work.
- 1. "Similar" or "Sim" means comparable characteristics for items noted. Verify dimensions & orientation on
- 12. NOTATION MARKED 'TYP' SHALL BE CONSISTENT THROUGHOUT ALL SUCH REFERENCE NOMENCLATURE, SYMBOLS & DWGS. INDICATIONS OF LIKE OR SIMILAR KIND.
- 13. ALL DIMENSIONS ARE TO BE EXACT WITHIN 1/4" ALONG FULL HEIGHT & FULL WIDTH OF WALLS. CONTRACTOR SHALL NOT
- ADJUST ANY DIMENSIONS MARKED "CLEAR" OR "CLR" WITHOUT WRITTEN INSTRUCTION FROM THE ARCHITECT. 14. ALL DOORS ADJACENT TO WALLS ARE GIVEN AS 5" FROM THE FACE OF JAMB TO THE FACE OF FINISH OF ADJACENT WALL,
- TYP., U.O.N.
- 15. ALL FIRE-RATED EQUIPMENT & ASSEMBLIES WHERE REQUIRED, SHALL BEAR THE "UL" LABEL.
- 16. CONTRACTOR SHALL COORDINATE INSTALLATION OF N.I.C. ITEMS W/ OTHER TRADES. 17. (E) WORK SHOWN IS FOR REFERENCE ONLY. THE OWNER / ARCHITECT DO NOT GUARANTEE (E) CONDITIONS AS SHOWN ON
- 18. KEYNOTES USED ON THIS SET OF ARCH. DWGS. ARE FOR ASSEMBLIES, MATERIALS REFERENCES & NOTES. REFER TO THE
- KEYNOTE LISTS ON THE RESPECTIVE DWGS. FOR THE INFORMATION WHICH RELATES TO EACH KEYNOTE.
- 19. Provide solid backing for all wall mounted equipment & or accessories where required, exact location to BE DETERMINED PER EQUIPMENT / ACCESSORIES. CONTRACTOR TO FIELD VERIFY, COORDINATE & OBTAIN APPROVAL FROM ARCHITECT & TENANT / OWNER PRIOR TO CONSTRUCTION. SEE STRUCT. DWGS. FOR ALL SEISMIC ANCHORAGE & ASSOCIATED STRUCT. WORK WHERE OCCURS.

A. THRU PENETRATION IN 1 HR. FIRE-RATED PARTITION / WALL ASSEMBLY SHALL BE INSTALLED PER 2019 C.B.C. 714.3.1.1. & PROTECTED BY AN APPROVED PENETRATION FIRE STOP SYSTEM W/ F RATING OF NOT LESS THAN THE REQUIRED FIRE-RESISTANCE RATING OF THE PARTITION PENETRATED (2019 C.B.C. 714.3.1.2.) MEMBRANE PENETRATION AT PARTITION SHALL COMPLY W/ 2019 C.B.C. 714.3.2. SEE ELECT. & PLUMB. DWG. FOR PIPE, CONDUITS, CABLES, ETC. PENETRATIONS.

B. NOT USED.

C. DUCT PENETRATION THRU (1) HR. FIRE-RATED PARTITION / WALL SHALL BE PROTECTED W/ 1-1/2" HR. FIRE-RATED (UL-555) FIRE DAMPER (2019 C.B.C. 717.5.4). SEE MECH. DWG.


D. NOT USED.

ASSEMBLIES.

e. fire caulk all joints at thru & membrane penetrations at all fire-rated wall, roof - ceiling & floor

LEGENDS

LOCATION -



REFLECTED CEILING PLAN NOTES

- 1. CONTRACTOR SHALL COORDINATE W/ ALL TRADES INVOLVED & OR PREPARE COMPOSITE SHOP DWGS. TO ENSURE CLEARANCES FOR FIXTURE, DUCTS, CEILINGS, ETC. NECESSARY TO MAINTAIN THE SPECIFIED FINISH CEILING HEIGHT ABOVE THE FINISH FLOOR SLAB AS NOTED ON THE DWGS. CLARIFY CONFLICTS W/ ARCHITECT, & MECH. & ELECT. ENGINEERS. CEILING GRID FRAMING CHANGES DUE TO CEILING CONFLICTS WILL NOT BE ACCEPTED.
- 3. NOT USED.
- 4. ALL EQUIP, INCLUDING LIGHT FIXTURES, LENSES, ETC., SHALL BE (N) & FREE OF DEFECTS. ANY & ALL DAMAGED, DENTED OR DEFECTIVE EQUIP., WHETHER IT BE BUILDING STANDARD OR SPECIAL ORDER, WILL BE REJECTED & REPLACED AT NO ADDITIONAL COST TO THE OWNER.
- i. All Switches shall be 48" Above finished floor u.o.n. on the plans. All heights are given from top or rough FLOOR TO CENTERLINE OF COVER PLATE, MOUNTED VERTICALLY. WHEN MORE THAN ONE SWITCH IS SHOWN AT THE SAME LOCATION, THEY SHALL BE GANGED, & FINISHED W/ A ONE PIECE COVER PLATE.

6. NOT USED. 7. NOT USED.

- 8. ALL LIGHT SWITCHING SHALL CONFORM TO TITLE 24 REQUIREMENTS. SEE ELECT. DWGS.
- 9. CONTRACTOR TO PROVIDE APPROPRIATE SUSPENSION SYSTEM FOR INTEGRATION OF FIXTURE & SUPPORT MEMBER. 10. ELECT., MECH. & PLUMB. SYSTEM (LIGHTING, SWITCHING, ETC.) SHALL CONFORM TO APPLICABLE CODES. 11. ELECT. CONTRACTOR SHALL FURNISH & INSTALL ALL FIXTURES, ASSOCIATED TRIMS & LIGHT FIXTURE.
- 12. DESIGN-BUILD SUBCONTRACTORS SHALL BE RESPONSIBLE FOR PREPARING DWGS., CALCULATIONS & /OR DOCUMENTATION AS REQUIRED.

CLG.

C.O.

COL.

COMP.

CONC.

CONN

C.M.U.

L OR C.L. CENTERLINE

CLEAR

CEILING

CLEAN OUT

CONCRETE

COMPOSITION

CONNECTION

CONTINUOUS

CONTRACTOR

COUNTERSUNK

COLD WATER

DOUGLAS FIR

DIMENSION

DOWNSPOU^{*}

DRAWINGS

ELECTRICAL

ELEVATION

ENCLOSURE

EQUIPMENT

FXHAUST

EXTERIOR

FLAT BAR

FIRE ALARM

FIBERGLASS

FLOOR DRAIN

FOUNDATION

FIRE HYDRANT

FLAT HEAD

FINISH

FLOOR

FACE OF

FACE OF FINISH

FIRE EXTINGUISHER

FIRE HOSE CABINET

FINISHED OPENING

FACE OF CONCRETE

FIRE EXTINGUISHER CABINET

FIRE RETARDAN

FNAMFI

FOLIAL

EXPANSION JOINT

ELECTRIC PANEL BOARD

ELECTRIC WATER COOLER

ELECTRIC WATER HEATER

DOWN

DOOR

FACH

CLEAN OUT TO GRADE

DRINKING FOUNTAIN

COLUMN

CONCRETE MASONRY UNIT

ABBREVIATIONS					
A.B.	ANCHOR BOLT	F.O.M.	FACE OF MASONRY	PORC.	PORCELAIN
A.C.	ASPHALT CONCRETE	F.O.S.	FACE OF STUD	PR.	PAIR
A/C	AIR CONDITIONING	F.S.	FLOOR SINK	P.S.D.	POWDER SOAP DISPENSER
A.F.F.	ABOVE FINISH FLOOR	FTG.	FOOTING	PT.	POINT
A.T.	ACOUSTIC TILE	FRP	FIBERGLASS REINFORCED	P.T.D.	PAPER TOWEL DISPENSER
ADJ.	ADJUSTABLE		PLASTIC	PTN.	PARTITION
A.F.S.	AUTOMATIC FIRE SPRINKLER			P.V.C.	POLYVINYL CHLORIDE
ALUM.	ALUMINUM	GA.	GAUGE		
&	AND	GALV.	GALVANIZED	Q.T.	QUARRY TILE
L	ANGLE	G.I.	GALVANIZED IRON		
ANOD.	ANODIZED	GRD.	GROUND OR GRADE	(R)	RELOCATED
APPROX.	APPROXIMATELY	G.S.F.	GROSS SQUARE FEET	R.	RISERS
ARCH.	ARCHITECTURAL	G.V.	GATE VALVE	R.A.	RETURN AIR
ASPH.	ASPHALT	G.F.R.C.	GLASS FIBER REINFORCED	RAD.	RADIUS
@	AT		CONCRETE	R.C.P.	REINFORCED CONCRETE
		G.F.C.B.	GATE VALVE IN CONCRETE		PIPE
BD.	BOARD		BOX	RD.	ROUND
BLDG.	BUILDING	GYP.	GYPSUM	R.D.	ROOF DRAIN
BLKG.	BLOCKING			REC.	RECESSED
BM.	BEAM	HDR.	HEADER HARDWOOD	REF.	REFERENCE
B.O.	BOTTOM OF	HDWD.	HARDWOOD	REINF.	REINFORCED
B.O.J.	BOTTOM OF JOISTS	HDWR.	HARDWARE	REQ.	REQUIRED
BOTT.	BOTTOM	H.M.	HOLLOW METAL	RESIL.	RESILIENT
B.U.	BUILT-UP	HORIZ.	HORIZONTAL	R.H.	ROUND HEAD
		H.P.	HIGH POINT	R.H.	ROBE HOOK
CAB.	CABINET	HR.	HOUR	RM.	ROOM
CAD. PL.		H.R.C.	hose reel cabinet	RO.	ROUGH
C.A.	CATCH BASIN	H.S.B.	HIGH STRENGTH BOLT	R.O.	ROUGH OPENING
C.B.	CHALKBOARD	HT.	HEIGHT	R/W	RIGHT OF WAY
C.D.	CUP DISPENSER	H.T.D.	HANDICAP TOWEL	RWD.	REDWOOD
CEM.	CEMENT		DISPENSER	R.W.L.	rain water leader
CER.	CERAMIC	HTG.	HEATING		
C.F.C.I	CONTRACTOR FURNISHED,	H.W.	hot water	S.C.D.	SEAT COVER DISPENSER
	CONTRACTOR INSTALLED	H.W.D.	hot water dispenser	S.D.	
				SECT.	SECTION
C.G.	CORNER GUARD	I.D.	INSIDE DIAMETER	S.F.	SQUARE FOOT / FEET
	CHANNEL	INC.	INCLUDING	SHT.	SHEET
C.I.	CAST IRON	INV.	INVERT	SHTHG.	Sheathing
C.J.	CONSTRUCTION JOINT	INSUL.	INSULATION	SHLV.	SHELVE(S)
.		I.S.	INSIDE	SIM.	SIMILAR

INT.

K.O.

LAV.

LKR.

L.S.D.

MACH.

MAT.

MAX

M.B.

MECH.

MEMB.

MET.

MFR.

M.H.

M.S.

MULL.

N.I.C.

N.I.F.

O.C.

O.D.

OFF.

O.H.

OPP.

P.A.

P.D.F.

P.H.

PLAS.

P.LAM.

PLYWD.

PNI

POL.

OPNG.

O.F.C.I.

N.T.S.

K.P.

INTERIOR

JANITOR

KITCHEN

KNOCK-OUT

KICK PLATE

LAMINATE

LAVATORY

LOW POINT

LIOUID SOAP DISPENSER

LOCKER

LIGHT

MACHINE

MATERIAL

MAXIMUM

MECHANICAL

MEMBRANE

MANHOLE

MULLION

NFW

MFTAL

MACHINE BOLT

MANUFACTURER

MACHINE SCREW

NOT IN CONTRACT

OUTSIDE DIAMETER

OVERFLOW DRAIN

OWNER FURNISHED,

CONTRACTOR INSTALLED

POWDER DRIVE FASTENER

NET SQUARE FEET

NOT TO SCALE

ON CENTER

OFFICE

OVERHEAD

OPENING

OPPOSITE

PANIC BAR

PLATE

PLASTER

PLYWOOD

POLISHED

PANFI

PUBLIC ADDRESS

PHILLIPS HEAD

PROPERTY LINE

PLASTIC LAMINATE

JOINT

JUNCTION BOX

CAL GREEN NOTES

SINK OR SKETCH

SEE MECHANICAL

SHUT OFF VALVE

SPECIFICATIONS

STAINLESS STEEL

SERVICE SINK

STANDARD

STORAGE

SUSPENDED

TOWEL BAR

DISPOSAL

TOP OF

TREAD

TYPICAL

TELEPHONE

TOP OF SLAB

TOP OF WALL

TOILET PAPER

UNDERWRITERS

UNLESS OTHERWISE NOTED

VINYL COMPOSITION TILE

VITREOUS CLAY PIPE

LABORATORY

UNFINISHED

URINAL

VERTICAL

WITH

WOOD

VERIFY IN FIELD

WASTE BASKET

WAINSCOT

WORK POINT

WATERPROOF

WOOD SCREW

WINDOW WALL

WATER RESISTANT

WASTE RECEPTACLE

WEATHER STRIPPING

WELDED WIRE FABRIC

TOP AND BOTTOM

TOWEL DISPENSER

TOWEL DISPENSER &

TONGUE AND GROOVE

STEEL

STAIN

STRUCT. STRUCTURAL

SHEET METAL SCREW

SANITARY NAPKIN DISPOSAL

Sanitary napkin vendor

SEE PLUMBING DRAWINGS

SEE STRUCTURAL DRAWINGS

SHFFT MFTAL

DRAWINGS

S.M.

S.M.D.

SND

S.N.V.

S.O.V.

SPECS.

STD.

STL.

STN

STOR.

SUSP.

T.B.

T & G

T.O.S.

T.O.W.

T.P.

TRD.

TYP.

U.O.N.

V.C.T.

VERT.

W.B.

WAINS.

WD

W.R.

W.S.

W.W.

S.P.D.

FINISH NOTES

C.B.C. CHAPTER 8.

C.B.C. CHAPTER 14.

FLOORING, WOOD, COATINGS & THERMAL INSULATION:

HEALTH PUBLIC SPEC. 01350. (CEnC 4.504.4).

6. USE SOLVENT FREE ADHESIVES. (CEnC 4.504.2.1)

https://www.arb.ca.gov/drdb/ba/cur.html.

SHOWER / SHOWER TUB / TUB WALLS

C.R.C. R207.2 & R302.6)

SHALL BE COMPLIANT W/ VOC LIMITS (CEnC 4.504.2).

MIR LIMITS FOR ROC & OTHER TOXIC COMPOUNDS (CEnC 4.504.2.3)

5. USE LOW VOC, WATER BASED WOOD FINISHES (CEnC 4.504.2.2).

9. THERMAL INSULATION SHALL COMPLIES W/ VOC LIMITS. SEE

ATTACHED PER 2019 C.B.C. 1119A.2.

COMPOUND LIMITS (CEnC 4.504.3).

1. MAX. FLAME SPREAD CLASSIFICATION OF INTERIOR FINISH MATERIALS MUST COMPLY W/ 2019

2. MAX, FLAME SPREAD CLASSIFICATION OF EXTERIOR FINISH MATERIALS MUST COMPLY W/ 2019

1. CARPET HAS A FIRM CUSHION AND A MAX. PILE HEIGHT OF 1/2". CARPET IS TO BE SECURELY

2. 80% OF FLOOR AREA RECEIVING RESILIENT FLOORING WHERE OCCURS, SHALL COMPLY W/ THE

CARPET, & CARPET SYSTEMS WHERE OCCURS SHALL COMPLY W/ VOC & OTHER TOXIC

VOC EMISSION LIMITS DEFINED IN THE COLLABORATIVE FOR HIGH PERFORMANCE SCHOOLS

(CHPS), HIGH PERFORMANCE PRODUCTS DATABASE OR BE CERTIFIED UNDER THE RESILIENT

FLOOR COVERING INSTITUTE (FRCI) FLOOR SCORE PROGRAM, OR MEET CALIFORNIA DEPT. OF

3. FINSH MATERIALS, I.E. ADHESIVE, SEALANTS, CAULKS, PAINTS & COATINGS WHERE OCCURS,

4. AEROSAL PAINTS & COATINGS WHERE OCCURS, SHALL BE COMPLIANT W/ PRODUCT WEIGHTED

7. USE LOW VOC. FORMALDEHYDE-FREE COMPOSITE WOOD MATERIALS. PARTICLE BOARD & MDF

SHOWER &/ OR SHOWER/ TUB WALLS SHALL HAVE A SMOOTH, HARD, NONABSORBENT SURFACE,

E.G. CERAMIC TILE, FIBERGLASS, ETC. O/ A MOISTURE RESISTANT UNDERLAYMENT, EG. WATER

RESISTANT GYP. BD., GREEN BD., ETC. TO A HEIGHT OF 72" ABOVE THE FLOOR / DRAIN INLET (2019

8. CHECK MOISTURE CONTENT MATERIALS FOR WALLS & FLOORS BEFORE ENCLOSURE (CEnC

PROTECT ANNULAR SPACES AROUND OPENINGS IN PLATES AT EXTERIOR WALL (CALGREEN 4.406.1). USE CONT. SEALANT.

1. PRACTICE PROPER INSULATION INSTALLATION (FORM CF2R-ENV-23H).

- COVER DUCT OPENINGS / AIR DISTRIBUTION OPENINGS DURING CONSTRUCTION (CEnC 4.504.1). 2. HVAC SHALL COMPLY W/ HEATING & AIR CONDITIONING SYSTEM DESIGN PER CEnC 4.507.2. 3. USE DUCT MASTIC ON ALL DUCT JOINTS: CMC 603.10.
- 4. HVAC DUCT LEAKAGE: MAX. 10% FOR SYSTEM EXTENSIONS OR MAX. 5% FOR REPLACEMENTS (CEnC 150.2(b)1D)
- 5. VENT BATHROOM EXHAUST TO OUTSIDE W/ HUMIDISTAT CONTROL UNLESS WHOLE HOUSE VENTILATION (CEnC 4.506.1).
- 6 CLEAN ALL DUCTS BEFORE OCCUPANCY.

I. CONTRACTOR TO PROVIDE (N) HOMEOWNER MANUAL INCLUDING GREEN MEASURES & BENEFITS PER CEnC 4.410.1.

2. CONTRACTOR TO SEPARATE HAZARDOUS WASTE & ORGANIC WASTE FROM OTHER WASTE DURING DEMOLITION & CONSTRUCTION.

21060 HOMESTEAD RD, CUPERTINO , CA 95014 T: 650.665.0439

DATE

02/20/2025

CONSULTANT BEHROOZ NEMATI

PROJECT

N

APPROVED ARCHITECTURAL & SITE APPLICATION:

REV DATE DESCRIPTIO PLANNING

SHEET TITLE

GENERAL NOTES

SHEET NO.

21060 HOMESTEAD RD, CUPERTINO, CA 95014

02/20/2025




CONSULTANT BEHROOZ NEMATI

PROJECT

REV	DATE	DESCRIPTIO
	2.25.2025	PLANNING
2	07/31/2025	PLANNING
		6.1.202
PRO	JECT NO.	F21
SHF	FT TITI F	

EX. SITE PLAN A1.0 & DEMOLITION AREA

A1.0A



21060 HOMESTEAD RD, CUPERTINO, CA 95014 T: 650.665.0439

DATE

02/20/2025

CONSULTANT


PROJECT

(2) APPROVED ARCHITECTURAL & SITE APPLICATION:

28

DESCRIPTIO PLANNING PLANNING 07/31/2025 PROPOSED SITE PLAN

A1.0B



21060 HOMESTEAD RD, CUPERTINO, CA 95014 T: 650.665.0439

02/20/2025

New Single

(2)

APPROVED ARCHITECTURAL & SITE APPLICATION:

REV	DATE	DESCRIPTIO)
	2.25.2025	PLANNING	G
2	07/31/2025	PLANNING	;
			_
			_
			_
		6.1.20)2
PRO	JECT NO.	F2	21
SHE	ET TITLE	ROPOSED SITE PLAN	_

PROPOSED SITE PLAIN (ONLY SETBACKS ARE SHOWN)

A1.0B/1


UNDER FLOOR AREA CALCULATION


J :	509.42 SQF
K :	137.214 SQF
<u> </u>	364.102 SQF
M :	506.174 SQF THE NEW ADDITION AREA


TOTAL LIVABLE AREA: 1516.9 SQF

FIRST FLOOR AREA CALCULATION

A : 768.64 SQF
B: 622.71 SQF
C: 600.2 SQF
D : 33.6 SQF
E: 71.67 SQF
F : 533.45 SQF
ATTACHED ADU: 755.92 SQ.FT G: 222.47 SQF
TOTAL LIVABLE AREA: 2096.84 SQF
TOTAL INHABITANT AREA: 400 SQ.FT
H: 200 SQF : 200 SQF GARAGE AREA 400 SQ.FT
TOTAL IST FLOOR AREA: 3252.76 SQF







BNDS

21060 HOMESTEAD RD, CUPERTINO , CA 95014 T: 650.665.0439

DAT

02/20/2025



CONSULTANT BEHROOZ NEMATI

PROJECT

Story New Single Family House

ADDDOVED ADCUITECTUDAL OF CITE ADDUICATION


REV	DATE	DESCRIPTION
	2.25.2025	PLANNING
2	07/31/2025	PLANNING
		6.1.2021
PR∩	IFCT NO	F21.1

HEET TITLE


AREA CALCULATION

SHEET NO

A1.0C




DESCRIPTIO		DATE	ΕV
PLANNING		2.25.2025	
PLANNING	5	07/31/202!	
,			
6.1.202			
F21		JECT NO.	RO.
	FIRST FLOOR PLAN	ET TITLE	HEE




21060 HOMESTEAD RD, CUPERTINO, CA 95014 T: 650.665.0439



V	DATE	DESCRIPTIO
	2.25.2025	PLANNING
	07/31/2025	PLANNING
		_
		6.1.202
(O.	JECT NO.	F21
ΙΕΙ	ET TITLE	OND ELOOD DI ANI





21060 HOMESTEAD RD, CUPERTINO , CA 95014 T: 650.665.0439

02/20/2025


CONSULTANT BEHROOZ NEMATI

PROJECT


RCP

A1.5

SCALE: 3/16" = 1'-0 "



FRONT ELEVATION



LEFT SIDE ELEVATION

SCALE: 3/16" = 1'-0 "

BNDS

21060 HOMESTEAD RD, CUPERTINO , CA 95014 T: 650.665.0439

DATE

02/20/2025

CONSULTANT


PROJECT


728 NEWHALL RD. BURLINGAME CA 9401

APPROVED ARCHITECTURAL & SITE APPLICATION:


REV	DATE	DESCRIPTIO
	2.25.2025	PLANNING
2	07/31/2025	PLANNING
•		6.1.202
PRO	JECT NO.	F21
SHE	ET TITLE	
		TIONS

[°] A2.0





GARAGE FRONT ELEVATION



RIGHT SIDE ELEVATION

SCALE: 3/16" = 1 "

BNDS

21060 HOMESTEAD RD, CUPERTINO , CA 95014 T: 650.665.0439

02/20/2025

CONSULTANT


PROJECT

728 NEWHALL RD. BURLINGAME CA 94010

APPROVED ARCHITECTURAL & SITE APPLICATION:

REV	DATE	DESCRIP	TIO
	2.25.2025	PLANN	IING
2	07/31/2025	PLANN	ING
		6.	1.202
PRO	JECT NO.		F21
SHE	ET TITLE	ELEVATIONS	


A2.1



21060 HOMESTEAD RD, CUPERTINO , CA 95014



REV	DATE		DESCRIPTION
	2.25.2025		PLANNING
2	07/31/2025		PLANNING
			6.1.2021
PRO	JECT NO.		F21.1
SHE	ET TITLE		
		SECTIONS	



Type Mark	Count	Width	Height	TEMPERED	TYPE
W1	1	8' - 0"	7' - 0"	YES	FIX.
W2	1	3' - 0"	7' -0"	YES	CAS.
W3	1	10' - 6"	4' -0"	YES	SL.
W4	1	5' - 0"	16' -10"	YES	CAS. FIX
W5	1	5' - 0"	4' -6"		CAS.
W6	3	3' - 0"	7' -0"		CAS.
W7	4	6' - 0"	4' -6"		CAS.
W8	1	8' - 0"	2' -6"		CAS.
W9	3	2' - 0"	2' -6"		CAS.
W10	1	3' - 0"	4' -6"		CAS.
W11	1	2' - 6"	7' -0"		CAS.
W12	4	2' - 6"	4' - 0"		
W13	1	6' - 0"	6' -0"	YES	CAS.
W14	2	2' - 6"	5' - 0"		
W15	1	5' - 9"	5' -10"		
W16	3	5' - 0"	4' -0"		CAS.
W17	1	6' - 0"	4' -0"		CAS.
W18	1	3' - 6"	7' -0"		
W19	1	2' - 0"	4' -0"		CAS.
W20					

Window Schedule

D1	1
D3	6
D4	8
D4	8
D5	1
D6	1
D8	2
D9	1
D10	1
D11	1

	Door	Schedule			
Type Mark	Count	Width	Height	TEMPERED	TYPE
D1	1	6' - 0"	8' - 0"	MAIN DOOR	CAS.
D3	6	6' - 0"	8' - 0"	CLOSET DOOR	CAS.
D4	8	2' - 8"	8' - 0"	DOOR	CAS.
D4	8	2' - 8"	7' - 0"	DOOR	CAS.
D5	1	12' - 0"	8' - 0"	TEMPERED	CAS.
D6	1	14' - 0"	8' - 0"	TEMPERED B	IFOLD
D8	2	2' - 8"	8' - 0"	POCKET DOOR	CAS.
D9	1	8' - 0"	7' - 0"	EXTERIOR	CAS.
D10	1	10' - 0"	7' - 0"	INTERIOR CLOSET	SLID
D11	1	7' - 0"	7' - 0"	INTERIOR CLOSET	CAS.

BNDS

21060 HOMESTEAD RD, CUPERTINO , CA 95012 T: 650.665.0439

02/20/2025

CONSULTANT BEHROOZ NEMATI


PROJECT


APPROVED ARCHITECTURAL & SITE APPLICATION:

REV	DATE	DESCRIPTIO
	2.25.2025	PLANNING
2	07/31/2025	PLANNING
		6.1.202
PRO	JECT NO.	F21

WINDOWS & DOORS SCHEDULE


A7.0







PREVIOUSLY PROPOSED LEFT SIDE ELEVATION



REVISED PROPOSED LEFT SIDE ELEVATION


SCALE: 3/16" = 1 "

BNDS

21060 HOMESTEAD RD, CUPERTINO , CA 95014 T: 650 665 0439

ΛTE

02/20/2025



CONSULTANT BEHROOZ NEMATI

PROJECT

D. 94010

?) Story New Single Family House


APPROVED ARCHITECTURAL & SITE APPLICATION:

REV	DATE	DESCRIPTION
	2.25.2025	PLANNING
2	07/31/2025	PLANNING
		6.1.2021
PRO	JECT NO.	F21.1

LEFT ELEVATION COMPARISON


SHEET NO.

A3.1A




PREVIOUSLY PROPOSED REAR ELEVATION

REVISED REAR ELEVATION



PREVIOUSLY PROPOSED MAIN ELEVATION



REVISED MAIN ELEVATION

BNDS

21060 HOMESTEAD RD, CUPERTINO , CA 95014

DATE

02/20/2025



CONSULTANT BEHROOZ NEMATI

PROJECT

L RD.

2) Story New Single Family House


APPROVED ARCHITECTURAL & SITE APPLICATION:

REV	DATE	DESCRIPTION
	2.25.2025	PLANNING
2	07/31/2025	PLANNING
		6.1.202
PRO	JECT NO.	F21.
CHE	ET TITI E	

FRONT & REAR ELEVATIONS COMPARISON

SHEET N

A3.1B





WEST BIRD VIEW



NORTH WEST & SOUTH EAST ELEVATIONS



NORTH VIEW FROM EXTERIOR PATIO



WEST STREET VIEW



NORTH BIRD VIEW



WEST BIRD VIEW

21060 HOMESTEAD RD, CUPERTINO , CA 95014 T: 650.665.0439

DATI

02/20/2025



CONSULTANT BEHROOZ NEMATI

PROJECT

ALL RD. ME CA 94010

APPROVED ARCHITECTURAL & SITE APPLICATION

APPROVED ARCHITECTURAL & SITE APPLICATION:			
DATE		DESCRIPTION	
2.25.2025		PLANNING	
07/31/2025		PLANNING	
	DATE 2.25.2025	DATE	

PROJECT NO.

RENDERS

SHEET NO.

A3.1





EAST BIRD VIEW SOUTH BIRD VIEW



SOUTH STREET VIEW

21060 HOMESTEAD RD, CUPERTINO , CA 95014 T: 650 665 0439

DATI

02/20/2025



CONSULTANT BEHROOZ NEMATI

PROJECT

RD.

Story New Single Family House

APPROVED ARCHITECTURAL & SITE APPLICATION:

REV	DATE	DESCRIPTION
	2.25.2025	PLANNING
		6.1.2021


ET TITLE

RENDERS

2 ALTERNATIVEA PROPOSED


SHEET N

A3.2









outside	
1. SIZE:144*96 inon (3668*2438mm)	

2. Item: 75series thermal break aluminum folding door 5. Aluminum thickness, 2.0mm 4. Color: MATT black color powder coated

5. Glass. 5mm Lowe outside+27Argon gas+5mm, double tempered clear gass-

Sketch Map

Double layer tempered glass

0.32

0.2











From \$97.48/mo with shop Check your purchasing power

35 inch height (Residential)	40 inc
42 inch height (Commercial)	

REAR BALCONY'S RAILING



SLATPANEL OAK EXTERIOR COMPOSITE WOOD EFFECT WALL PANELS



ENTRY DOOR STAIN WOOD WITH METAL FRAME PAVERS WITH GRASS TURFSTONE WITH DECORATIVE



GARAGE DOOR- COLPAY CANYON RIDGE: COLLECTION MODERN SERIES



ENTRY PAVER- TECHO-BLOC



21060 HOMESTEAD RD, CUPERTINO , CA 95014 T: 650.665.0439

02/20/2025



CONSULTANT BEHROOZ NEMATI

PROJECT

APP	APPROVED ARCHITECTURAL & SITE APPLICATION:				
REV	DATE		DESCRIPTIO		
	2.25.2025		PLANNING		
2	07/31/2025		PLANNING		
			6.1.202		
PRO	JECT NO.		F21.		

MATERIAL BOARD

A3.3




5. Hardware: LSMA brand Multipoint lock, Black color

7 Tracks: low tracks

9 Design 1L3R, outswing

8. Without mesh and frame cover




STANDING SEAM METAL ROOFING


CLASSIC METAL ROOFING SYSTEM

MATT FINISH & BE NON REFLECTIVE

SMOOTH GRAY STUCCO

Layout possibilities





Color variation chart





ENTRY PAVER- TECHO-BLOC PATERN & COLOR

	ABBRE	$- \bigvee A$	TIONS			
	DESCRIPTION		DESCRIPTION			
AB AC AC BFL BW CC CC CC DDI DTLCT EUC),F FFGHL FFGBY HDINV JB	AGGREGATE BASE ASPHALT CONCRETE AREA DRAIN BACK OF CURB BACKFLOW PREVENTOR BOTTOM OF WALL CURB AND GUTTER CENTERLINE CENTERLINE SWALE CLEANOUT CONTROL POINT DRIVEWAY DROP INLET DETAIL ELECTRIC EDGE OF PAVEMENT ELEVATION EUCALYPTUS TREE EXISTING FINISH FLOOR FINISH GRADE FIRE HYDRANT FLOWLINE FENCE FACE OF CURB GRADE BREAK GUY WIRE HIGH POINT DUCTILE IRON PIPE INVERT JOINT POLE JUNCTION BOX (UTILITY)	LIP N(N) GB GE Y L LIP N(N) GB GE Y P P P P R R SDST S S S W C F G D S P Y Y P P R R SDST S S S S C F G D S P X Y P X X X X X X X X X X X X X X X X	LIP OF GUTTER LOW POINT MONUMENT NEW ORIGINAL GROUND PULL BOX PG&E VAULT PROPERTY LINE POWER POLE PLASTIC PERFORATED PIPE PUBLIC SERVICE EASEMENT POLYVINYL CHLORIDE RIGHT OF WAY REINFORCED CONCRETE PIPE STORM DRAIN STORM DRAIN STORM DRAIN MANHOLE STANDARD SANITARY SEWER SANITARY SEWER SANITARY SEWER TOP OF CURB TOP OF CURB TOP OF GRATE TOP OF BECK TOP OF SLAB TOP OF PAVEMENT TOP OF WALL TYPICAL VITRIFIED CLAY PIPE WHITE LINE STRIPE WALKWAY WATER METER WATER			

LEGEND

PROPOSED

EXISTING

DESCRIPTION

PROPERTY LINE

		PROPERTY LINE	wat
——— F———	——— F———	FILL AREA LIMIT	app
C	C	CUT AREA LIMIT	Cor • sec
102	102	CONTOUR	• and
	W	WATER LINE	• stro
—————————————————————————————————————	———SD— —	STORM DRAIN PIPE (SOLID)	9.
———— SS ————	——— SS ———	SANITARY SEWER PIPE	No. bacl
—————————————————————————————————————	———SUD→	SUBDRAIN PIPE (PERFORATED)	10.
OH e,T,TV	OH e,T,TV	OVERHEAD UTILITIES WITH POLE	con
———— G ————	——— G ———	GAS LINE	app 11.
— Е —	—— Е ——	ELECTRIC LINE (UNDERGROUND)	Worl
JT	JT	JOINT TRENCH (UNDERGROUND)	Cool The
SLV	SLV	STREET LIGHT VAULT	a. and dam
○ SSCO	● SSCO	SANITARY SEWER CLEANOUT	vicir b. 13.
	•	SANITARY SEWER MANHOLE	con: Worl
\odot	•	STORM DRAIN MANHOLE	and 15.1
		SURVEY CITY MONUMENT	http enti Plec
	\nearrow	ELECTROLIER	rem floo
WM	™ WM	WATER METER	prot 14. pave
		TREE WITH TRUNK	sew stor 15. star Wat
	xx	6' WOODEN FENCE	16. subi 17.
×102.23	102.23	SPOT ELEVATION	righ 18.
		TREE PROTECTION FENCE 5' TALL CHAIN LINK	19. houi
		EARTHSWALE	
		CONCRETE SWALE	
		AREA DRAIN/ INLET	
	\Rightarrow	OVERLAND RELEASE PATH	
	N V V V V V V V V V V V V V V V V V V V	GRADE TO DRAIN, 2% MIN. AWAY FROM H 1% MIN. FROM PROPERTY LINE TO S	

GRADING AND DRAINAGE PLANS NEW SINGLE FAMILY HOUSE 728 NEWHALL DR., BURLINGAME, CA 94010

APN: 028-142-310

PUBLIC WORKS CONDITIONS:

1. Any work in the City right—of—way, such as street, sidewalk area, public easements, utility easements, or use of the right-of-way such as placement of debris box or construction parking is required to obtain an Encroachment Permit prior to starting work. For requirements related to issuance of an Encroachment Permit, visit: https://www.burlingame.org/departments/public_works/encroachment_permit.php Work without the benefit of an encroachment permit will be charged double the permit fee.

2. All work within City right—of—way shall comply with City Standards and Details. Standard Details are available at: https://www.burlingame.org/departments/public_works/city_standard_details.php.

3. Public Works construction hours in the right-of-way are limited to weekdays and non-City Holidays between 8:00 a.m. and 5:00 p.m. This includes construction hauling. If applicant/contractor wishes to work beyond the normal construction hours, a waiver of working hour form may be submitted to the Public Works Department ten (10) working days in advance for review and approval by Public Works and Building Department.

4. For projects in the Burlingame Plaza, Broadway, and Burlingame downtown districts; construction in the public right—of—way is prohibited during the Holiday Shopping Moratorium period, from first Saturday of November through

5. For downtown Burlingame Avenue projects, per City of Burlingame Municipal Code 12.05, any work within the public right—of—way shall require approval from the Public Works Department and shall comply with the following special conditions, specifications, details, and construction moratorium.

6. For Projects facing El Camino Real: Any work in the Caltran's right—of—way, such as street and sidewalk area is required to obtain an Encroachment Permit from Caltran prior to starting work. It is the applicant's responsibility

7. No structure shall be built into City's right—of—way, this includes all existing and overhang projections. On Paloma Avenue, this measurement is twelve feet (12') measured from face of curb.

8. FOR NEW SINGLE FAMILY OR SUBSTANTIAL REMODELS (GREATER THAN 50% REMODEL/ADDITION): Show on the site plan — (1) Replacement of ALL curb, gutter, driveway and sidewalk fronting site, (2) plug all existing sanitary sewer lateral connections and install a new [4" or 6"] lateral to sewer main including wye, (3) new water service to water meter, and when applicable, (4) water lines above 2" and all fire services of any size are to be installed by applicant and per city standard procedures and specification.

Confirm with applicant: If the location of the new sewer lateral and/or water service is at a new location: • All abandoned sewer laterals shall have wyes or saddles removed off the main and replace with new straight

• All abandoned existing water services, 2—inch or below, shall be cut and cap at the existing main connection and disconnect at service saddle. Abandon valve where applicable. • All abandoned existing water services, greater than 2", shall have tees removed at main and replaced with straight pipe per City standards and details.

9. Sewer Backwater Protection Certification is required for the installation of any new sewer fixture per Ordinance No. 1710. The Sewer Backwater Protection Certificate is required prior to the issuance of Building Permit and the

backwater device must be placed on private property 10. For remodel projects (less than 50% remodel) All damaged and displaced curb, gutter, sidewalk, and driveway approach fronting site must be replaced prior to final of Building Permit. A pre—inspection by Public Works of the condition of the sidewalk is recommended, but not required. However, if a pre-inspection is not conducted, the applicant/contractor waives the right to contest the limits of the repairs caused by the construction activities. 11. Front landscape (hardscape) improvements that are not shown on the plans, this will be subject to a Public Works inspection prior to building permit final to confirm that no encroachments exist beyond the property line. 12. If applicable, for large developments (4—units or more), or improvements in downtown area: Contractor shall coordinate a meeting with the City Public Works Engineering Inspector 48 hours prior to initiation of the site work.

a. Plan of work within City's right of way, including, but not limited to, hours of work, deliveries, traffic control and/or pedestrian access within public right of way, sidewalk issues, parking, storage, loading of materials, repair of damaged public facilities such as sidewalk, road pavement, etc., and coordination with City projects within the

b. Contractor shall provide field contact names and numbers of responsible field personnel. 13. The project shall comply with the City's NPDES permit requirements to prevent storm water pollution. All construction work shall be done in accordance with the most current APWA-AGC Standard Specifications for Public Works Construction, the California Stormwater Quality Association's Stormwater Best Management Practice Handbook, and the City of Burlingame Stormwater Management and Discharge Control Ordinance (Municipal Code Chapter 15.14). A copy of the Stormwater Construction Best Management Practices can be found at

http://www.flowstobay.org/brochures. Upon completion of the work, all stormwater protection measures shall be entirely removed and the right-of-way shall be left in as presentable a condition as existed before work started. Please be aware that during winter months (October 15th to April 15th) applicant/contractor are responsible to remove projects stormwater inlet protection device(s) (sandbags/filters/etc.) in the public right—of—way to prevent flooding during rain events, and reinstall devices once the rain event ends. All private property stormwater protection measures must be protected and repaired after each rain event

14. Per Municipal code section 18.08.090, no storm water or underground water draining from any lot, building, or paved area shall be allowed to drain to adjacent properties nor shall this water be connected to the city's sanitary sewer system. Regardless of the slope of the source property, such water shall drain to either artificial or natural storm drainage facilities by gravity or pumping. 15. All water lines connections to city water mains for services or fire line protection are to be installed per city

standard procedures and material specifications. Contact the City's Water Department for connection fees. Domestic Water Services 2" and over shall be installed by builder 16. If required, all fire services shall be installed by builder. All underground fire service connections shall be submitted as separate Underground Fire Service permit for review and approval.

17. All debris/garbage containers location shall be on property. No wet garbage fluid shall enter public right-of-way or the storm drain system.

18. Porta potty's must be placed on private property and are not allowed in the public right—of—way. 19. It is the responsibility of the owner and/or contractor to notify Underground Service Alert (USA) at least 48 hours before the start of any excavation work.

EARTHWORK TABLE

	FILL (CY)	CUT (CY)	IMPORT (CY)	EXPORT (CY)
MAIN HOUSE	0	164		
A.D.U.	0	21		
GARAGE	4	16		
DRIVEWAY	2	29		
PORCH/WKY	6	0		
SITE	0	12		
TOTAL	12	242	0	230

NOTE:

(E) TREE TO BE REMOVE

DRAIN SYSTEM

ROOF DOWN-SPOUT, CONNECTED TO STORM

1. EARTHWORK QUANTITIES ON THIS TABLE ARE FOR INFORMATION ONLY. CONTRACTORS ARE TO PERFORM THEIR OWN QUANTITY TAKE OFFS.

BASIS OF BEARINGS:

THE BEARING N 37°21'09" W OF NORTHERLY LINE OF NEWHALL RD., AS SHOWN ON CERTAIN RECORD OF SURVEY MAP, FILED FOR RECORD IN BOOK 19 OF L.L.S. MAPS AT PAGE 35, WAS USED AS THE BASIS OF BEARINGS SHOWN HEREON.

LOCATION MAP

PROJECT BENCHMARK:

REFERENCED TOWN OF HILLSBOROUGH BM: BM# 126. EL: 54.721' (NAVD88)

GEOTECHNICAL NOTES:

1. For compacted fill material and placement specifications see "GRADING" section, pages 7 and 8, of project Geotechnical report, (file no. SV1303), dated September 23,2014 by Silicon Valley Soils

2. Provide special inspection for compacted fill.

UTILITY NOTES:

1. UTILITY POINTS OF CONNECTION ARE 5' OUTSIDE OF BUILDING. SEE MECHANICAL AND PLUMBING DRAWINGS FOR UTILITY CONNECTION

2. CONTRACTOR SHALL BE RESPONSIBLE FOR THE VERIFICATION OF LOCATIONS OF ALL

- EXISTING UTILITIES IN THE FIELD. ALL CONTRACTORS SHALL CALL U.S.A. (1-800-227-2600) 48 HOURS BEFORE DIGGING AND OBTAIN AN IDENTIFICATION NUMBER.
- 3. COORDINATE UTILITIES SHOWN ON THESE SHEETS WITH INSTALLATION OF ELECTRICAL, TELEPHONE, CABLE TV AND GAS.
- 4. COORDINATE WATER LINE CONNECTION WITH CITY WATER COMPANY PRIOR TO
- CONNECTION TO WATER SYSTEM.
- 5. FOR GAS AND ELECTRICAL LOCATIONS, SEE PG&E MAPS.
- 6. ALL UTILITY TRENCHES SHOULD BE BACKFILLED WITH COMPACTED FILL IN ACCORDANCE WITH LOCAL REQUIREMENTS OR THE RECOMMENDATIONS IN THE SOILS REPORT. FILL MATERIAL SHOULD BE PLACED IN LIFTS NOT EXCEEDING 8 INCHES IN UNCOMPACTED THICKNESS AND SHOULD BE COMPACTED TO AT LEAST 90 PERCENT RELATIVE COMPACTION (ASTM D-1557, LATEST EDITION) BY MECHANICAL MEANS ONLY, EXCEPT WHERE LOCAL REQUIREMENTS SPECIFY HIGHER REQUIREMENTS. IF IMPORTED SAND IS USED AS BACKFILL, THE UPPER THREE FEET IN BUILDING AND PAVEMENT AREAS SHALL BE COMPACTED TO 95 PERCENT. THE UPPER 6 INCHES OF BACKFILL IN ALL PAVEMENT AREAS SHALL BE COMPACTED TO AT LEAST 95 PERCENT RELATIVE
- 7. SANITARY SEWER PIPE SHALL BE PVC SDR26 FOR ON SITE LINES. STORM DRAIN PIPE SHALL BE 12" REINFORCED CONCRETE PIPE (UNLESS OTHERWISE SHOWN).
- 8. SANITARY SEWER LATERAL SHALL BE 4" PVC AT MINIMUM SLOPE OF 0.02 WITH CLEANOUT.
- 9. WATER MAINS, SERVICES, METERS, FIRE SERVICES AND FIRE HYDRANTS BY CITY WATER COMPANY.
- 10. THE CONTRACTOR IS RESPONSIBLE TO HAVE ALL INSTALLATIONS INSPECTED AND APPROVED BY THE RESPECTIVE UTILITY COMPANY, MUNICIPALITY, OR SOILS ENGINEER PRIOR TO ANY BACK FILLING. (48 HOUR NOTICE).
- MATERIAL. COMPACTION TO MEET LOCAL AGENCIES REQUIREMENTS. 12. THE CONTRACTOR IS RESPONSIBLE FOR COORDINATION OF CONSTRUCTION WITH THE RESPECTIVE UTILITY AGENCIES, ALLOWING 48 HOURS PRIOR TO THE NEED FOR INSTALLATIONS.

11. CONSULT PARTICIPATING UTILITIES, SOILS ENGINEER, AND THE CITY FOR APPROVED BACK FILL

- 13. ALL TRENCHES, CONDUITS, AND BOXES ARE SHOWN SCHEMATICALLY.
- 14. CONTRACTOR TO VERIFY ALL INVERTS AND LOCATIONS OF UTILITIES PRIOR TO CONSTRUCTION.

INDEX OF DRAWINGS

PROJECT SITE

TITLE	SHEET
COVER SHEET	C - 1
GRADING AND DRAINAGE PLAN	C-2
DETAILS	C - 3
EROSION CONTROL PLAN	C-4
CONSTRUCTION BMP	C-5

GRADING AND DRAINAGE NOTES:

- 1. SURFACE WATER SHALL BE DIRECTED AWAY FROM ALL BUILDINGS INTO DRAINAGE SWALES, GUTTERS, STORM DRAIN INLETS AND DRAINAGE SYSTEMS.
- 2. ALL ROOF DOWNSPOUTS SHALLI BE DISCONNECTED TO ON SITE
- 3. ON SITE STORM DRAIN LINES SHALL CONSIST OF SOLID PVC-SDR35 MINIMUM OR BETTER.
- 4. STORM DRAIN INLETS SHALL BE PRECAST CONCRETE, CHRISTY U23 TYPE OR EQUIVALENT.

UTILITY NOTE:

THE UTILITIES EXISTING ON THE SURFACE AND SHOWN ON THIS DRAWING HAVE BEEN LOCATED BY FIELD SURVEY. ALL UNDERGROUND UTILITIES SHOWN ON THIS DRAWING ARE FROM RECORDS OF THE VARIOUS UTILITY COMPANIES AND THE SURVEYOR DOES NOT ASSUME RESPONSIBILITY FOR THEIR COMPLETENESS, INDICATED LOCATION, OR SIZE. RECORD UTILITY LOCATION SHOULD BE CONFIRMED BY EXPOSING THE UTILITY.

NOTE:

CONSTRUCTION HOURS IN THE CITY PUBLIC RIGHT-OF-WAY ARE LIMITED TO WEEKDAYS AND NON-CITY HOLIDAYS BETWEEN 8:00 A.M. AND 5:00 P.M.


GEOTECHNICAL REVIEW:

GRADING AND DRAINAGE PLANS SHALL BE REVIEWED AND APPROVED BY THE PROJECT GEOTECHNICAL/ SOILS ENGINEER. GEOTECHNICAL/ SOILS ENGINEER TO PROVIDE AND FURNISH LETTER OF APPROVAL TO CITY.

NOTICE TO CONTRACTORS

CONTRACTOR TO NOTIFY U.S.A. (UNDERGROUND SFRVICE ALERT) AT 800-227-2600 A MINIMUM OF 2 WORKING DAYS BEFORE BEGINNING UNDER-GROUND WORK FOR VERIFICATION OF THE LOCATION AND DEPTH OF UNDERGROUND UTILITIES.





1534 CAROB LANE LOS ALTOS, CA 94024 TEL: (650) 941-8055 FAX: (650) 941-8755

OWNER / DEVELOPER:

COPYRIGHT (C) 2021 SMP ENGINEERS

CIVIL ENGINEERS

2 07/31/2025

PLANNING

05/27/2025 AS SHOWN PREPARED BY:

S.S. CHECKED BY: S.R.

225049


Sheet: 1 OF 5

NOTE:


- 1. Any work in the City right-of-way, such as placement of debris bin in street, construction parking, work in sidewalk area, public easements, and utility easements, is required to obtain an Encroachment Permit prior to starting work. Porta potty's are not allowed to be placed in the City right—of—way. Work without the benefit of an Encroachment Permit will be double the permit fee.
- Construction hours in the City Public right—of—way are limited to weekdays and non-City Holidays between 8:00 a.m. and 5:00 p.m. for all activities (including hauling).
- All water lines connections to city water mains for services or fire line protection are to be installed per city standard procedures and material specifications. Contact the city Water department for connection fees. If required, all fire services and services 2" and over will be installed by builder. All underground fire service connections shall be submitted as separate Underground Fire Service permit for review and approval.
- Sewer Backwater Protection Certification is required for the installation of any new sewer fixture per Ordinance No. 1710. The Sewer Backwater Protection Certificate is required prior to the issuance of Building Permit.

NOTE:


CONTRACTOR SHOULD VERIFY LOCATION OF SEWER LATERAL AND EASEMENT.




EXISTING IMPERVIOUS AREA TOTAL = 4106 SQFT




PROPOSED IMPERVIOUS AREA TOTAL = 5636 SQFT




EXISTING IMPERVIOUS AREA TO BE REPLACED WITH NEW IMPERVIOUS AREA TOTAL = 2941 SQFT






CHANNEL DRAIN TYPICAL DETAIL



94010

PLANNING



SMP CIVIL ENGINEERS LAND SURVEYORS

1534 CAROB LANE LOS ALTOS, CA 94024 TEL: (650) 941-8055 FAX: (650) 941-8755

OWNER / DEVELOPER:

COPYRIGHT (C) 2021 SMP ENGINEERS CIVIL ENGINEERS

94010

2 07/31/2025





Gueid Razani

05/27/2025 AS SHOWN PREPARED BY:

S.S. CHECKED BY:

3 OF 5





_STAPLE AS REQUIRED

- The entrance shall be maintained in a condition that will prevent

tracking or flowing sediment onto public rights—of—way. This may

demand, and repair and/or clean out any measures used to trap

require periodic top dressing with additional stone as conditions

- All sediment spilled, dropped, washed, or tracked onto public

- When necessary, wheels shall be cleaned to remove sediment

an area stabilized with crushed stone, which drains into an

prior to entrance onto public rights—of—way. This shall be done at

STABILIZED CONSTRUCTION ENTRANCE

(TO BE MAINTAINED)

rights-of-way shall be removed immediately.

approved sediment trap or sediment basin.

CONCRETE WASHOUT AREA

WEIGHT IN CORNERS


N.T.S.

.12 MIL PLASTIC

STACKED HAY BALES (2)



1. Place fiber roll in key trench 3" deep and place excavated soil on uphill or flow side of the roll. 2. On slopes and hillsides, fiber rolls shall be abutted at the ends and not overlapped. Place alternate stakes on both sides of the roll, every 6'.



N.T.S PONDING HEIGHT FIBER ROLLS

3. Install fiber roll 12" from limit of grading

-EMBED FIBER ROLL 3"-5" INTO SOIL. (SEE FIBER ROLL DETAIL E5) SLOPE DROP PROVIDE 1' WIDE BY 6" (2.5:1)INLET DEEP SEDIMENT TRAP TRENCH AROUND INLET. FOSSIL FILTER -SECTION A - A

FIBER ROLL.

579-8819

1. PLACE FIBER ROLLS AROUND THE INLET CONSISTENT WITH BASIN SEDIMENT BARRIER DETAIL ON THIS SHEET. FIBER ROLLS ARE TUBES MADE FROM STRAW BOUND W/ PLASTIC NETTING. THEY ARE APPROX. 8" DIA. AND 20 -16 FT. LONG

2. FIBER ROLL INSTALLATION REQUIRES THE PLACEMENT AND SECURE STAKING OF THE FIBER ROLL IN A TRENCH, 3" DEEP, DUG ON CONTOUR. RUNOFF MUST NOT BE ALLOWED TO RUN UNDER OR AROUND

CIVIL ENGINEERS LAND SURVEYORS 3. THE TOP OF THE STRUCTURE (PONDING HEIGHT) MUST BE WELL BELOW THE GROUND ELEVATION DOWNSLOPE TO PREVENT RUNOFF FROM BY-PASSING 1 1534 CAROB LANE INLET. EXCAVATION OF A BASIN ADJACENT

LOS ALTOS, CA 94024 TO THE DROP INLET OR A TEMPORARY TEL: (650) 941-8055 DIKE ON THE DOWNSLOPE OF THE FAX: (650) 941-8755 STRUCTURE MAY BE NECESSARY. 4. FOSSIL FILTERS SHALL BE INCORPORATED IN ALL CATCH BASINS AND

FIELD INLETS 24" AND LARGER AND SHAL BE INSTALLED PER MANUFACTURER OWNER / DEVELOPER: SPECIFICATIONS. FOSSIL FILTERS ARE AVAILABLE FROM KRISTAR ENTERPRISES INC., 422 LARKFIELD CENTER, SUITE 271

> COPYRIGHT (C) 2021 SMP ENGINEERS


SMP


CIVIL ENGINEERS

94010

STORM INLET SEDIMENT TRAP-FIBER ROLLS

SANTA ROSA, CA 95403, PHONE (800)





EROSION AND SEDIMENT CONTROL NOTES AND MEASURES

1. The facilities shown on this Plan are designed to control Erosion and sediment during the rainy season, October 1st to April 30. Facilities are to be operable prior to October 1 of any year. Grading operations during the rainy season, which leave denuded slopes shall be protected with erosion control measures immediately following grading on the slopes.

2. This plan covers only the first winter following grading with assumed site conditions as shown on the Erosion Control Plan. Prior to September 15, the completion of site improvement shall be evaluated and revisions made to this plan as necessary with the approval of the city engineer. Plans are to be resubmitted for city approval prior to September 1 of each subsequent year until site improvements are accepted by the city. 3. Construction entrances shall be installed prior to commencement

of grading. All construction traffic entering onto the paved roads must cross the stabilized construction entranceways. 4. Contractor shall maintain stabilized entrance at each vehicle access point to existing paved streets. Any mud or debris tracked onto public streets shall be removed daily and as required by the

5. If hydroseeding is not used or or is not effectively 10/10, then other immediate methods shall be implemented, such as Erosion control blankets, or a three—step application of: 1) seed, mulch, fertilizer 2) blown straw 3) tackifier and mulch.

6. Inlet protection shall be installed at open inlets to prevent sediment from entering the storm drain system. Inlets not used in conjunction with erosion control are to be blocked to prevent entry of sediment.

7. Lots with houses under construction will not be hydroseeded Erosion protection for each lot with a house under construction shall confirm to the Typical Lot Erosion Control Detail shown on this sheet. 8. This erosion and sediment control plan may not cover all the situations that may arise during construction due to unanticipated

field conditions. Variations and additions may be made to this plan

in the field. Notify the city representative of any field changes. 9. This plan is intended to be used for interim erosion and sediment control only and is not to be used for final elevations or permanent improvements.

10. Contractor shall be responsible for monitoring erosion and sediment control prior, during, and after storm events.

11. Reasonable care shall be taken when hauling any earth, sand, gravel, stone, debris, paper or any other substance over any public street, alley or other public place. Should any blow, spill, or track over and upon said public or adjacent private property, immediately remedy shall occur.

12. Sanitary facilities shall be maintained on the site.

N.T.S.

10. During the rainy season, all paved areas shall be kept clear of earth material and debris. The site shall be maintained so as to minimize sediment laden runoff to any storm drainage systems, including existing drainage swales and water courses.

13. Construction operations shall be carried out in such a manner that erosion and water pollution will be minimized. State and local laws concerning pollution abatement shall be complied with.

14. Contractors shall provide dust control as required by the appropriate federal, state, and local agency requirements. 13. With the approval of the city inspector, erosion and sediment controls maybe removed after areas above them have been stabilized.

MAINTENANCE NOTES

F. Rills and gullies must be repaired.

1. Maintenance is to be performed as follows: A. Repair damages caused by soil erosion or construction at the end of each working day.

B. Swales shall be inspected periodically and maintained as needed. C. Sediment traps, berms, and swales are to be inspected after each storm and repairs made as needed.

D. Sediment shall be removed and sediment traps restored to its original dimensions when sediment has accumulated to a depth of

E. Sediment removed from trap shall be deposited in a suitable area and in such a manner that it will not erode.

2. All existing drainage inlets on St. George Lane within the limit of the project , shall be protected with sand bags during construction. See detail. Sand bag inlet protection shall be cleaned out whenever sediment depth is one half the height of one sand bag.

3. Existing concrete ditch sediment trap shall be cleaned out routinely during construction.

PLANNING 07/31/2025



05/27/2025 Scale: AS NOTED

PREPARED BY: S.S. CHECKED BY:

S.R.

225049

Sheet: 4 OF 5




Construction Best Management Practices (BMPs)

Construction projects are required to implement the stormwater best management practices (BMP) on this page, as they apply to your project, all year long.

Clean Water. Healthy Community.

Materials & Waste Management



Non-Hazardous Materials

- ☐ Berm and cover stockpiles of sand, dirt or other construction material with tarps when rain is forecast or if not actively being used within
- ☐ Use (but don't overuse) reclaimed water for dust control.

Hazardous Materials

- ☐ Label all hazardous materials and hazardous wastes (such as pesticides, paints, thinners, solvents, fuel, oil, and antifreeze) in accordance with city, county, state and federal regulations.
- ☐ Store hazardous materials and wastes in water tight containers, store in appropriate secondary containment, and cover them at the end of every work day or during wet weather or when rain is forecast.
- ☐ Follow manufacturer's application instructions for hazardous materials and be careful not to use more than necessary. Do not apply chemicals outdoors when rain is forecast within 24 hours.
- ☐ Arrange for appropriate disposal of all hazardous wastes.

Waste Management

- ☐ Cover waste disposal containers securely with tarps at the end of every work day and during wet weather.
- ☐ Check waste disposal containers frequently for leaks and to make sure they are not overfilled. Never hose down a dumpster on the construction site.
- ☐ Clean or replace portable toilets, and inspect them frequently for leaks and spills.
- ☐ Dispose of all wastes and debris properly. Recycle materials and wastes that can be recycled (such as asphalt, concrete, aggregate base materials, wood, gyp board, pipe, etc.)
- ☐ Dispose of liquid residues from paints, thinners, solvents, glues, and cleaning fluids as hazardous waste.

Construction Entrances and Perimeter

- ☐ Establish and maintain effective perimeter controls and stabilize all construction entrances and exits to sufficiently control erosion and sediment discharges from site and tracking off site.
- ☐ Sweep or vacuum any street tracking immediately and secure sediment source to prevent further tracking. Never hose down streets to clean up tracking.

Equipment Management & Spill Control




Maintenance and Parking

- ☐ Designate an area, fitted with appropriate BMPs, for vehicle and equipment parking and storage.
- ☐ Perform major maintenance, repair jobs, and vehicle and equipment washing off site.
- ☐ If refueling or vehicle maintenance must be done onsite, work in a bermed area away from storm drains and over a drip pan or drop cloths big enough to collect fluids. Recycle or dispose of fluids as hazardous waste
- ☐ If vehicle or equipment cleaning must be done onsite, clean with water only in a bermed area that will not allow rinse water to run into gutters, streets, storm drains, or surface waters.
- ☐ Do not clean vehicle or equipment onsite using soaps, solvents, degreasers, or steam cleaning equipment.

Spill Prevention and Control

- ☐ Keep spill cleanup materials (e.g., rags, absorbents and cat litter) available at the construction site at all times.
- ☐ Inspect vehicles and equipment frequently for and repair leaks promptly. Use drip pans to catch leaks until repairs are made.
- ☐ Clean up spills or leaks immediately and dispose of cleanup materials properly.
- ☐ Do not hose down surfaces where fluids have spilled. Use dry cleanup methods (absorbent materials, cat litter, and/or rags).
- Sweep up spilled dry materials immediately. Do not try to wash them away with water, or bury them.
- ☐ Clean up spills on dirt areas by digging up and properly disposing of contaminated soil.
- ☐ Report significant spills immediately. You are required by law to report all significant releases of hazardous materials, including oil. To report a spill: 1) Dial 911 or your local emergency response number, 2) Call the Governor's Office of Emergency Services Warning Center, (800) 852-7550 (24 hours).

Earthmoving




- ☐ Schedule grading and excavation work during dry weather.
- ☐ Stabilize all denuded areas, install and maintain temporary erosion controls (such as erosion control fabric or bonded fiber matrix) until vegetation is established.
- ☐ Remove existing vegetation only when absolutely necessary, and seed or plant vegetation for erosion control on slopes or where construction is not immediately planned.
- ☐ Prevent sediment from migrating offsite and protect storm drain inlets, gutters, ditches, and drainage courses by installing and maintaining appropriate BMPs, such as fiber rolls, silt fences, sediment basins, gravel bags, berms, etc.
- ☐ Keep excavated soil on site and transfer it to dump trucks on site, not in the streets.

Contaminated Soils

- ☐ If any of the following conditions are observed, test for contamination and contact the Regional Water Quality Control Board:
- Unusual soil conditions, discoloration, or odor.
- Abandoned underground tanks.
- Abandoned wells
 - Buried barrels, debris, or trash.

Paving/Asphalt Work



- ☐ Avoid paving and seal coating in wet weather or when rain is forecast, to prevent materials that have not cured from contacting stormwater runoff.
- ☐ Cover storm drain inlets and manholes when applying seal coat, tack coat, slurry seal, fog seal, etc.
- ☐ Collect and recycle or appropriately dispose of excess abrasive gravel or sand. Do NOT sweep or wash it into gutters.
- ☐ Do not use water to wash down fresh asphalt concrete pavement.

Sawcutting & Asphalt/Concrete Removal


- ☐ Protect nearby storm drain inlets when saw cutting. Use filter fabric, catch basin inlet filters, or gravel bags to keep slurry out of the storm drain system.
- ☐ Shovel, abosorb, or vacuum saw-cut slurry and dispose of all waste as soon as you are finished in one location or at the end of each work day (whichever is
- ☐ If sawcut slurry enters a catch basin, clean it up immediately.

Concrete, Grout & Mortar **Application**




- ☐ Store concrete, grout, and mortar away from storm drains or waterways, and on pallets under cover to protect them from rain, runoff, and wind.
- ☐ Wash out concrete equipment/trucks offsite or in a designated washout area, where the water will flow into a temporary waste pit, and in a manner that will prevent leaching into the underlying soil or onto surrounding areas. Let concrete harden and dispose of as garbage.
- ☐ When washing exposed aggregate, prevent washwater from entering storm drains. Block any inlets and vacuum gutters, hose washwater onto dirt areas, or drain onto a bermed surface to be pumped and disposed of properly.

Landscaping



- ☐ Protect stockpiled landscaping materials from wind and rain by storing them under tarps all year-round.
- ☐ Stack bagged material on pallets and under cover.
- ☐ Discontinue application of any erodible landscape material within 2 days before a forecast rain event or during wet weather.


Painting & Paint Removal




Painting Cleanup and Removal

- ☐ Never clean brushes or rinse paint containers into a street, gutter, storm drain, or stream.
- ☐ For water-based paints, paint out brushes to the extent possible, and rinse into a drain that goes to the sanitary sewer. Never pour paint down a storm drain.
- ☐ For oil-based paints, paint out brushes to the extent possible and clean with thinner or solvent in a proper container. Filter and reuse thinners and solvents. Dispose of excess liquids as hazardous waste.
- dry stripping and sand blasting may be swept up or collected in plastic drop cloths and disposed of as trash.
- ☐ Chemical paint stripping residue and chips and dust from marine paints or paints containing lead, mercury, or tributyltin must be disposed of as hazardous waste. Lead based paint removal requires a statecertified contractor.


Dewatering



- ☐ Discharges of groundwater or captured runoff from dewatering operations must be properly managed and disposed. When possible send dewatering discharge to landscaped area or sanitary sewer. If discharging to the sanitary sewer call your local wastewater treatment plant.
- ☐ Divert run-on water from offsite away
- ☐ When dewatering, notify and obtain approval from the local municipality or storm drain. Filtration or diversion through a basin, tank, or sediment trap
- ☐ In areas of known or suspected contamination, call your local agency to determine whether the ground water must be tested. Pumped groundwater may need to be collected and hauled off-site for



- ☐ Paint chips and dust from non-hazardous



from all disturbed areas.

- before discharging water to a street gutter may be required.
- treatment and proper disposal

Storm drain polluters may be liable for fines of up to \$10,000 per day!

SMP CIVIL ENGINEERS LAND SURVEYORS

1534 CAROB LANE LOS ALTOS, CA 94024 FAX: (650) 941-8755

OWNER / DEVELOPER

COPYRIGHT (C) 2021 SMP ENGINEERS CIVIL ENGINEERS


CONSTRUCTION E
NEW SIN

Sucid Razani

PREPARED BY: S.S. CHECKED BY: S.R.

225049

5 OF 5



W. Jeffrey Heid Landscape Architect

1465 Winzer Place Gilroy, Ca. 95020 tel 408 691-5207 email wiheidasla@qmail.com

OWNERSHIP AND USE OF DRAWINGS

All drawings, specifications and copies thereof furnished by W. Jeffrey Heid Landscape Architect are and shall remain its property. They are to be used only with respect to this Submission or distribution to meet official regulatory requirements or for other purposes in connection with the Project is not to be construed as publication in

common law, copyright or other reserved rights.

REVISED 4/3/25 REVISED 5/27/25

2 07/31/2025

PLANNING

IZADDOOST/ DELPAZIRIAN RESIDENCE

MEHDI IZADDOOST AND AMIR DELPAZIRIAN 728 NEWHALL ROAD BURLINGAME, CA. 94010

MASTER PLANTING PLAN

2025|2

	Califor	nia Water	Efficient Lar	ndscape	Worksheet		
Reference Evapotranspiration (ET _o)		42.8			T		0.55
Hydrozone # / Planting Description ^a	Plant Factor (PF)	Irrigation Method ^b	Irrigation Efficiency (IE) ^c	ETAF (PF/IE)	Landscape Area (Sq. Ft.)		Estimated Total Water Use (ETWU) ^d
Regular Landscape	Areas	I				I	
#1 high water lawn		Overhead	0.75	0.93	175	163	4334
#2 low water	0.3	Drip	0.81	0.37	350	130	3440
#3 low water		Drip	0.81	0.37	25	9	
#4 low water		Drip	0.81	0.37	70	26	688
#5 low water		Drip	0.81	0.37	335	124	3292
			0.75	0.00		0	C
		***************************************	0.75	0.00		0	C
			0.75	0.00		0	C
			0.75	0.00		0	
			0.75	0.00		0	C
			0.75	0.00		0	C
			0.75	0.00		0	C
			0.75	0.00		0	C
			0.75	0.00		0	c
			0.75	0.00		0	C
			0.75	0.00		0	C
		***************************************	0.75	0.00		0	C
			0.75	0.00		0	C
			0.75	0.00		0	C
			0.75			0	
				Totals	955	452	12000
Special Landscape A	reas					I =	
				1		0	
				1		0	
				1		0	
				Totals	0	0	
				liulais		/U Total	12000
		N //-	vimum Alleri	od ///ot-	r Allowance (i		†

ETAF Calculations Regular Landscape Areas

Average ETAF for Regular Landscape Areas must be 0.55 or Total ETAF x Area below for residential areas, and 0.45 or below for non-residential Average ETAF

All Landscape Areas Total ETAF x Area Total Area Average ETAF

HYDROZONE LEGEND

Hydrozone #1: 175 sf/high water lawn Hydrozone #2: 350 sf/low water Hydrozone #3: 25 sf/low water Hydrozone #4: 70 sf/low water Hydrozone #5: 335 sf/low water

Total: 955 sf

0.45 Non-Residential

0.55 Residential

0.81 Drip 0.75 Overhead

^a Hydrozone # / Planting Description e.g.

2.) Low water use planting

3.) Medium water use planting

d ETWU (Annual Gallons Required) =

year to gallons per square foot per year

e MAWA (Annual Gallons Allowed) =

(Eto) (0.62) [(ETAF x LA) + ((1-ETAF) x SLA)]

Where 0.62 is a conversion factor to change acre-inches per acre per

Where 0.62 is a conversion factor to change acre-inches

per acre per year to gallons per square foot per year, LA is

the total regular landscape area in square feet, SLA is the total special landscape area in square feet, and ETAF is

0.55 for residential areas and 0.45 for non-residential

Eto x 0.62 x ETAF x Area


1.) Front lawn

b Irrigation Method 1.) Overhead Spray

^c Irrigation Efficiency 1.) 0.75 for Overhead Spray

2.) 0.81 for Drip

2.) Drip



(E) HOUSE RIDGE 83.91 W. Jeffrey Heid Landscape Architect


1465 Winzer Place Gilroy, Ca. 95020 tel 408 691-5207 email wjheidasla@qmail.com

OWNERSHIP AND USE OF DRAWINGS

All drawings, specifications and copies thereof furnished by W. Jeffrey Heid Landscape Architect are and shall remain its property. They are to be used only with respect to this Project and are not to be used on any other project. Submission or distribution to meet official regulatory requirements or for other purposes in connection with the Project is not to be construed as publication in derogation of W. Jeffrey Heid Landscape Architect , common law, copyright or other reserved rights.

REVISED 4/3/25 REVISED 5/27/25

2 07/31/2025




IZADDOOST/ DELPAZIRIAN RESIDENCE

MEHDI IZADDOOST AND AMIR DELPAZIRIAN 728 NEWHALL ROAD BURLINGAME, CA. 94010

HYDROZONE PLAN

2025|2

IRRIGATION LEGEND Rainbird ESP weather based controller with rain sensor - verify placement in garage - run control wires from controller to irrigation main within schedule 80 conduit I'' brass shut off valve Febco #825Y | reduced pressure backflow preventer with lockable cover verify location point of connection and install per manufacturers specifications I'' schedule 40 pvc mainline - min, depth 18" Rainbird PEB series control valves with in line pressure reducer set to 35 psi and Y filter Schedule 40 pvc lateral lines - min. depth 12" Schedule 40 pvc sleeving - verify placement under patio and walks Rainbird Xeribuq | aph pressure compensating emitters set on $\frac{1}{2}$ drip line (2 emitters to each I gallon plan, 3 to each 5 gallon and 4 for larger) locate at opposite sides of the rootball install flush end valve at the end of each drip line run Hunter MP Rotator with 6" pop up 1) Verify water source and placement of backflow preventer. 2) Verify site water pressure at 65 psi - notify architect prior to construction if found to be different. 3) Verify electrical source and placement of controller. 4) Verify operation of system before backfilling trenches. Drip line to be secured to grade with stakes and covered with final mulch. 5) System layout is diagrammatic, actual field conditions will dictate final layout, addition of drip line, etc. 6) Verify control wire placement and operation of valves. 7) Verify placement of rain sensor in field. 8) Contractor shall be responsible for setting and monitoring irrigation system to apply adequate water for (E) HOUSE establishment. but to eliminate runoff and soil saturation. RIDŒ 83.91 9) Contractor to submit maintenance and irrigation schedule to owner at completion of installation and maintenance/warrantee period. 10) Contractor shall verify location of all underground utilities prior to any trenching or excavation.



W. Jeffrey Heid Landscape Architect

1465 Winzer Place Gilroy, Ca. 95020 tel 408 691-5207 email wjheidasla@qmail.com

OWNERSHIP AND USE OF DRAWINGS

All drawings, specifications and copies thereof furnished by W. Jeffrey Heid Landscape Architect are and shall remain its property. They are to be used only with respect to this Submission or distribution to meet official regulatory requirements or for other purposes in connection with the Project is not to be construed as publication in derogation of W. Jeffrey Heid Landscape Architect , common law, copyright or other reserved rights.

REVISED 5/27/25



No. 2235 Signature EXPIRATION DATE: 06/30/2025

> IZADDOOST/ DELPAZIRIAN RESIDENCE

MEHDI IZADDOOST AND AMIR DELPAZIRIAN 728 NEWHALL ROAD BURLINGAME, CA. 94010

IRRIGATION PLAN

WITH 1/4" TUBING, STAKE AND XERI-BUG

1. USE RAIN BIRD XERIMAN TOOL XM-TOOL TO INSERT BARB CONNECTOR DIRECTLY INTO 1/2" POLYETHYLENE TUBING.

11) Verify and coordinate installation of sleeving and/or mainline and lateral lines access under all pavement.

12) Contractor shall provide all necessary safety precautions throughout construction. This shall include

specific directions regarding trenching and location of the irrigation mainline. Placement of the mainline

1) SINGLE-OUTLET BARB INLET X BARB OUTLET

(1) SINGLE-OUTLET BARB INLET X BARB

RAIN BIRD XERI-BUG EMITTER

(5)½" SELF-PIERCING BARB CONNECTOR: RAIN BIRD SPB-025

RAIN BIRD XF SERIES TUBING OR

RAIN BIRD XBS BLACK STRIPE

RAIN BIRD XT-700 XERI-TUBE OR

CONTROL VALVE DETAIL

OUTLET EMITTER:

③ ½" DISTRIBUTION TUBING: RAIN BIRD XQ TUBING

6 1/2" POLYETHYLENE TUBING:

2 UNIVERSAL ½" TUBING STAKE: RAIN BIRD TS-025

(LENGTH AS REQUIRED)

RAIN BIRD XERI-BUG EMITTER 5/8" POLYETHYLENE TUBING:

RAIN BIRD XF SERIES TUBING OR RAIN BIRD XT-700 XERI-TUBE OR 3) RAIN BIRD XBS BLACK STRIPE TUBING

near two Redwood trees at the rear yard, shall be approved in the field by the project arborist or

landscape architect. Trenching shall be done by hand. Cutting tree roots shall be avoided unless

ackslash 1) See arborist report prepared by Heartwood Consulting Arborists, dated May 22, 2025 for

signage and barriers.

TREE PROTECTION

approved by the project arborist.

IN THE FOLLOWING MODELS:

XERI-BUG INTO 1/2-INCH TUBING

NOTES:
1. USE RAIN BIRD XERIMAN TOOL XM-TOOL TO INSERT EMITTER DIRECTLY INTO §" POLYETHYLENE TUBING.
2. RAIN BIRD XERI-BUG BARB X BARB EMITTERS ARE AVAILABLE

XB-05PC 0.5 GPH XB-10PC 1.0 GPH XB-20PC 2.0 GPH

2. SHOULD THE EMITTER BECOME DISLODGED UNREGULATED FLOW 3. RAIN BIRD XERI-BUG BARB X BARB EMITTERS ARE AVAILABLE

IN THE FOLLOWING MODELS: XB-05PC 0.5 GPH XB-10PC 1.0 GPH XB-20PC 2.0 GPH

BARB CONNECTOR INTO 1/2" TUBING



PROJECT ARBORIST

MATTHEW FRIED - ISA NO. MA-4851B matthew@heartwoodarborists.com 650-542-8733

ARBORIST NOTES

TREE INVENTORY DATE: 5/12/2025

TREE PROTECTION MARKUP BY: **MATTHEW FRIED (ISA NO. MA-4851B)**

BASE DRAWING:

Irrigation Plan (Sheet L3) prepared by Jeffrey Heid, dated April 3, 2025

REFER TO SHEET T-1.2 FOR TREE PROTECTION REQUIREMENTS

LEGEND

PROTECTED TREE

NON-PROTECTED TREE


TREE (REMOVE)

TREE PROTECTION **FENCE**

TREE INVENTORY & ASSESSMENT TABLE

*TRUNK DIAMETERS OF OFFSITE TREES ARE VISUAL ESTIMATES

Tree#	Protected	Preserve / Remove	Species	Trunk dia. (in.)	Health	Structure	Impact Level	Comments	
1	Yes	Remove	Norway maple Acer platanoides	4	Poor	Poor	NA	Red/puple cultivar	
2	Yes	Remove	Coast redwood Sequoia sempervirens	62	Good	Good	NA		
3	No	Remove	Black acacia Acacia melanoxylon	6, 5, 4, 4, 4	Good	Poor	NA	Stump sprout origin	
4	Yes	Preserve	Coast redwood Sequoia sempervirens	50	Good	Good	Low	DBH estimated due to access restrictions	
5	Yes	Preserve	Coast redwood Sequoia sempervirens	48	Good	Good	Low	DBH estimated due to access restrictions	
6	Yes	Remove	Coast live oak Quercus agrifolia	32	Good	Good	NA		
7	No	Remove	Giant dracaena Cordyline australis	8, 8	Fair	Fair	NA		
8	No	Remove	Sweetgum Liquidambar styraciflua	8	Good	Fair	NA	Codominant at 5 ft	
9	Yes	Preserve	Sweetgum Liquidambar styraciflua	28	Good	Poor	Low/ Moderate	Offsite tree topped for overhea	



9401 ORNIA AME 28

Revised

05/23/2025 11:33:14 AM

SCALE: AS SHOWN

PROTECTION

TREE

PLAN

SHEET 1 of 2

BIV

TREE PROTECTION REQUIREMENTS

--PRECONSTRUCTION PHASE---

1.TREE PROTECTION FENCES.

- FENCES SHALL BE INSTALLED AT THE LOCATIONS AND DISTANCES SHOWN ON SHEET T-1. FENCES SHALL CONFORM TO THE SPECIFICATION AT RIGHT.

THE AREA WITHIN THE FENCE IS THE TREE PROTECTION ZONE (TPZ).

2.TREE PROTECTION VERIFICATION

NOTIFY THE PROJECT ARBORIST AFTER TREE PROTECTION MEASURES HAVE BEEN INSTALLED. THE PROJECT ARBORIST SHOULD INSPECT THE MEASURES TO VERIFY THEIR COMPLIANCE.

3.MEETING WITH PROJECT ARBORIST

PRIOR TO BEGINNING ANY WORK OR DEMOLITION, ALL CONTRACTORS INVOLVED WITH THE PROJECT SHOULD ATTEND A PRE-CONSTRUCTION MEETING WITH THE PROJECT ARBORIST

•REVIEW THE TREE PROTECTION GUIDELINES, ACCESS ROUTES, STORAGE AREAS, AND WORK PROCEDURES WILL BE DISCUSSED

•IDENTIFY ANY POTENTIAL CLEARANCE PRUNING THAT MAY BE REQUIRED TO ACCOMMODATE

•THE GENERAL CONTRACTOR OR PROJECT MANAGER IS RESPONSIBLE FOR SCHEDULING THIS MEETING.

-DEMOLITION PHASE-

4.WHEN DEMOLISHING EXISTING FEATURES WITHIN TPZS, START WORK CLOSE TO TREES AND MOVE BACKWARD, LIMITING EQUIPMENT TO STILL-PAVED AREAS.

-CONSTRUCTION PHASE-

5. MAINTAIN TREE PROTECTION FENCES AROUND ALL TPZS AND INSPECT DAILY FOR DAMAGE AND PROPER FUNCTION.

6. DO NOT REMOVE, ADJUST, OR WORK INSIDE ANY TPZ WITHOUT CONSULTING THE PROJECT ARBORIST.

7. ANY WORK WITHIN ANY TPZ MUST BE APPROVED BY THE PROJECT ARBORIST PRIOR TO BEGINNING THE TASK.

8. ROOT MANAGEMENT

•IF ROOTS OVER 1" IN DIAMETER ARE ENCOUNTERED WHEN EXCAVATING IN ANY LOCATION: •HAND-DIG THE EDGE NEAREST THE TRUNK TO THE FULL DEPTH OF THE FEATURE BEING INSTALLED OR TO A DEPTH OF 3 FEET, WHICHEVER IS SHALLOWER.

•ROUTE CONDUIT AND OTHER FEATURES AROUND AND BETWEEN ROOTS WHEN POSSIBLE.

•IF ROOTS 1-2 INCHES IN DIAMETER MUST BE CUT, SEVER THEM CLEAN AND SQUARE AT UNDAMAGED TISSUE USING BYPASS PRUNERS FOR A SHARP SAW.

•IF ROOTS OVER 2" MUST BE CUT, STOP WORK IN THAT AREA AND CONTACT THE PROJECT ARBORIST IMMEDIATELY FOR GUIDANCE.

•THE PROJECT ARBORIST WILL INSPECT THE EXPOSED ROOT(S) TO ASSESS THE IMPACT OF CUTTING AND OVERSEE/DOCUMENT ANY APPROVED ROOT CUTTING.

•EXPOSED ROOTS AND UPPER 3 FEET OF TRENCH WALLS SHALL BE COVERED WITH 3-4 LAYERS OF BURLAP OR ABSORBENT FABRIC AND KEPT MOIST UNTIL BACKFILLED.

9. PRUNING / TRIMMING


ANY PRUNING OF ANY LIMBS OR ROOTS OVER 2" DIAMETER MUST BE SUPERVISED BY THE PROJECT ARBORIST.

-POST-CONSTRUCTION PHASE---

10. POST-CONSTRUCTION REMEDIAL TREATMENTS AND/OR MAINTENANCE MAY BE PRESCRIBED BY THE PROJECT ARBORIST NEAR THE END OF THE PROJECT. ANY DIRECTIVES WILL BE SITE-SPECIFIC AND TAILORED TO:

- •THE OBSERVED DISRUPTIVENESS OF CONSTRUCTION ACTIVITIES
- •TREE CONDITION AND RESPONSE TO CONSTRUCTION
- •TIME OF YEAR AND RECENT WEATHER

SEE SHEET T-1.1 for Fence Locations





TREE PROTECTION

URBAN TREE FOUNDATION © 2014 Modified by Heartwood Consulting Arborists



PROJECT ARBORIST MATTHEW FRIED - ISA NO. MA-4851B matthew@heartwoodarborists.com

650-542-8733

TREE PROTECTION


Revised

05/23/2025 11:33:32 AM

SCALE: AS SHOWN

SHEET 2 of 2

PLAN



 Ties are to be <u>loosely</u> installed so the tree can move when shaken.